PLANTING SCHEDULE

S1 Lawn

Plant Name	Specification	% mix	Area/m²	G's/ p m2	Total Grams
Emorsgate EG22 Strong Lawn Grass Mixture	Seed mix	-	4536	25	113400
Total					**114.5kg**

S2- Swale Planting

Plant Name	Specification	% mix	Area/m²	G's/ p m2	Total Grams
Emorsgate EM8 Meadow Mixture for Wetlands	Seed mix	-	492	4	1968
Total					**2kg**

W1-Woodland planting

Plant Name	Specification	% mix	Area/m²	G's/ p m2	Total Grams
Emorsgate EW1 Woodland Mixture	Seed mix	-	882	4	3528
Total					**3.5kg**

W2-Wildflower mix

Plant Name	Specification	% mix	Area/m²	G's/ p m2	Total Grams
Emorsgate EM2F Standard General Purpose Wild Flowers	Seed mix	-	5426	1.5	8139
Total					**8.2kg**

O1- Ornamental Planting

Plant Name	Specification	% mix	Area/m²	G's/ p m2	Total Plants
Artemisia schmidtiana 'Silver Mound'	*2L, container grown, full pot*	20	346	5	1732
Hydrangea paniculata	*2L, container grown, full pot*	15	260	5	1299
Lavandula angustifolia 'Hidcote'	*2L, container grown, full pot*	15	260	5	1299
Santolina chamaecyparissus	*2L, container grown, full pot*	10	173	5	866
Salvia 'Dark Night'	*2L, container grown, full pot*	10	173	5	866
Deschampsia cespitosa	*2L, container grown, full pot*	10	173	5	866
Hebe Youngii	*1.5 L pot,container grown,10-20cm*	10	173	5	866
Pittosporum tenuifolium	*3L pot,container grown,50-60cm*	10	173	5	866
Total m2	**1,732**	100	**-**		**8660**

H1-Proposed Hedgerow — To be planted in double staggered row

Plant Name	Specification	% mix	Linear m	Density p l/m	Total Plants
Crataegus monogyna	*1+1 bare root, 40-60cm whip*	20	63	6	378
Corylus avellana	*1+1 bare root, 40-60cm whip*	20	63	6	378
Acer Campestre	*1+1 bare root, 40-60cm whip*	15	47	6	284
Prunus Spinosa	*1+1 bare root, 40-60cm whip*	20	63	6	378
Ilex Aquifolium	*1+1 bare root, 40-60cm whip*	25	79	6	473
Total linear m	**315**	100			**1890**

Trees

Plant Name	Specification	% mix	m	density p m	Total Plants
Acer campestre (Ac)	*14-16cm Girth,Root Ball*	-	-	As Shown	**24**
Betula pendula (Bp)	14-16cm Girth,Root Ball	-	-	As Shown	27
Salix caprea (Sc)	*10-12cm Girth,Root Ball, Multistemmed*	-	-	As Shown	11
Prunus avium(Pa)	*10-12cm Girth,Root Ball*	-	-	As Shown	17
Malus sylvestris(Ms)	*10-12cm Girth,Root Ball*	-	-	As Shown	18
Sorbus aucuparia (Sa)	*10-12cm Girth,Root Ball*	-	-	As Shown	14
Salix alba (Sal)	*12-14cm Girth,Root Ball*	-	-	As Shown	8
Red James Grieve Apple Trees (Rjg)	*Semi-Vigoruous Tree (Rootstock M26)*	-	-	As Shown	10
Invincible Pear Trees (Ipt)	*Vigoruous Tree (Quince A)*	-	-	As Shown	9
Nabella Cherry Trees (Nct)	*More-Vigoruous Tree (Colt)*	-	-	As Shown	13
Total					**151**

NOTES:
1. Do not scale from this drawing.
2. Always work to noted dimensions.
3. All dimensions are in millimetres unless otherwise stated.
4. All setting out, levels and dimensions to be agreed on site.
5. The dimensions of all materials must be checked on site before being laid out.
6. This drawing must be read with the relevant specification clauses and detail drawings.
7. Order of construction and setting out to be agreed on site.

LOCATION PLAN

KEY

- S1-Lawn
- S2-Swale Planting
- W1-Woodland planting
- W2-Wildflower mix
- O1-Ornamental Planting
- Mown Grass Path
- Proposed Tree
- Proposed Orchard Tree
- Existing Tree
- Proposed Native Hedge
- Existing Hedge
- Flood Area
- P1-Pedestrian Asphalt
- P2-Vehicular Asphalt
- P3-Concrete Paving Flags
- P4-Concrete Parking Setts (Grey)
- Grasscrete (with Seed Mix)
- Parking Court
- Hedgehog Access
- Bird Box
- Bat Box
- Fallen Log

Revision	Date	Description	Drawn	Apprvd.
P01	30/09/25	First Issue	SL	CF

© THIS DRAWING IS COPYRIGHT PROTECTED AND MAY NOT BE REPRODUCED IN WHOLE OR PART WITHOUT WRITTEN AUTHORITY FROM THE OWNER.

Client: Williams Homes Ltd,

Project: Clawdd Poncen Corwen

Drg Title: Planting Plan

Created on	Created by	Approved by
05.09.25	TI	SR

Scale	Size	Workstage
1:500	A1	S3

LandStudio

Drg No. 501-LST-XX-XX-DR-L-0301

Suitability

Revision P01

© Land Studio Limited